Mob: 8595045022

GST:- 09CRPPP2056R2ZQ

Pawan Sharma

SHIV

CONSTRUCTION

ADD: I 96, Alpha 2 Greater Noida (U.P)

Email: SHIVCONSTRUCTION0933@GMAIL.COM	
Ref. No	Date
Rate of This Construction is @ 1850/- SFT For This	
Construction .	

- Cement –Wonder Plus Cement To Be Used concrete 1:1.5:3
- Pcc in foundation 1:4:8 100 mm thick.
- Steel Rathi TMT bar to Be used.

- Electrical work Wiring , switch ,socket, Should (Haveles) Condut PIPE.
- Plumbing work 3",4" Used for construction in Supreme PIPE Heavy Brass Tap, Used Divater For Bathroom.
- Shuttring Ply To be Used.
- Sever Line Pipe Should Be used In 6" Pipe in 2
 Chamber
- Tile Work Floor to Be used Tile Size 4' *4' (
 Varmuda Tile Used) .
- Main Gate Steel Gate As Per Drawing To Be
 Used .
- Front Balcony Used Iron Steel Railling.

- Stair Case Area used Iron steel Railling .
- Paint 2 Coat Putty ,1 Coat Primer 2 coat Plastic
 Paint
- Paint Front Elevation Apex Paint To Be Used .
- Plaster Should Be Dust For All Construction
- One Piece (CERA BRAND) English Sheet Should Be Used for Toilet.
- Ceiling Height Upto 10ft for finish floor level.
- Outer Main boundary wall 230 mm Brick Work.
- Staircase Area To Be Used Graynight Stone &
 Double Moulding Upto Range 130/150 .
- Teak Wooden Chowkat to Be Used.
- Flass Door With Both Side Sunmica With Handle Lock For Main Entrance Gate.

- Kitchen Wall Area 5 ft Tile To be Used.
- Kitchen Counter Slab To Be Used Granite With Double
 Moulding .
- Bathroom Wall tile height upto slab level 2' * 4'
- Bathroom Floor Tile 2' * 4'.
- Window Palla 1 Side Jalli And 1 Side Glass (Blue Sppayard)to Be Used .
- Perrapit Wall Height 3.6' to Be used
- Slab Concret Provide Rmc .& Mixture Machine.

Remark:-

- 18% Gst Extra To Be Paid Online Payment.
- Ceiling Plaster not Providing .

Payment Condition:

10% Advanced